FIRST STAGE QUALITY CONTROL TEST DATA

CONFIDENTIAL

APPROVE (QA.Dept.Mgr.)	APPROVE (Dev. test SM)	CHECK	REPORT
QA 30 APR 2026	DEV.TEST 30 APR 2026 Anuwat J.	Dev.Test 30 APR 2026 Teerawat S.	Dev.Test 30 APR 2026 Narasak.Y
REPORT NO. :		SAM-25-760-0144	

Model Name	MXY-5J105VF-PA1
Development rank	IXA
Pilot production date	6-Apr-26
Mass production date	6-May-26
Shipping date	TBC

Power supply : 1 ϕ , 50 Hz , 230 V.
Comp.model : SVB220FZYMC-L1×2.4
Ref.weight : R32 = 2400 g.
C / T size : φ4.0 ×φ2.8 × 100
Reference design specification no. : 702-RA-25090

Indoor unit prod.date : MSZ-LN25VG2V-SC3×5 (Unit Rishi)
-Lot size : - Units
Outdoor unit prod.date 6-Apr-26 Line : D2
-Lot size : 64P00001-64P00005 5 Units
Period of test 9-21 Apr'2025

Reference Product standard : ISO 16358-1:2013
Reference Capacity and Performance test standard : ISO 5151:2017 + Amd 1:2020
Reference Sound test standard : ISO 3744:2025,ISO 3745:2012 + Amendment 1 :2017
Reference Safety test standard : IEC 60335-1:2020 + A1:2025,IEC 60335-2-40:2024
Reference Other test standard : -

1.Test result :

Classification of Evaluate Item			Outline of Evaluate Condition and Principal Standard Value	Development Test result (Final)			Pilot Sampling Test result			
Test	Item	Detail		Qty	Judg		Qty	Judg		
Cooling Capacity and General Performance	Cooling capacity Rated	Room temp.	Spec. 1 ϕ , 50 Hz , 230 V Target	-	OK	Referent test report no: DEV-25-760-0128	1	OK	S / N : 25DC2785,25DC2780A,25DC2781B,25DC2783C,25DC2784D/64P00003 [RA-12A,RA-12B]	
		In DB27.0 °c,WB19.0 °c	Q = 10500 W Q ≥ 97.2 %						Capacity = 10918.0 W (103.981%) ✓	
		Out DB35.0 °c , WB24.0 °c	P = 3088 W P ≤ 105.0 %						Power Input = 3001 W (97.183%) ✓	
			EER = 3.40 W/W EER ≥ 97.2 %						EER = 3.638 W/W (107.000%) ✓	
			CSPF = 6.42 W/W SEER ≥ 97.2 %						CSPF = 6.61 W/W (102.960%)	
			Comp. Hz =73.0Hz. , Td = 94.0°C						Comp. Hz = 73.0Hz. , Td = 92.7C	
			Extension pipe length = 7.5m.						Extension pipe length = 7.5 m.	
	Cooling capacity Half	Room temp.	Spec. 1 ϕ , 50 Hz , 230 V Tolerance	-	OK	Referent test report no: DEV-25-760-0128	1	OK	S / N : 25DC2785,25DC2780A,25DC2781B,25DC2783C,25DC2784D/64P00003 [RA-12A,RA-12B]	
		In DB27.0 °c,WB19.0 °c	Capacity = 5459 W (Rate /.2) Q ± 546.0 W and ± 5 % of actual rate						Capacity = 5035.0 W (96.117%) ✓	
		Out DB35.0 °c , WB24.0 °c	Power input 905 W P ≤ - %						Power input = 843.0 W (93.149%) ✓	
			EER = 5.80 W/W EER ≥ - %						EER = 5.973 W/W (102.983%) ✓	
			Comp. Hz = 27.0Hz. , Td = 67.0°C						Comp. Hz = 27.0Hz. , Td = 68.1 °C	
	Cooling Overload	In32.0/23.0 °c,Out 43.0/26.0 °c	During 2 Hr. protector does not work and Pd < 4.17 Mpa	-	OK	Referent test report no: DEV-25-760-0128	-	OK	Referent test report no: DEV-25-760-0128	
	Cooling Overload	In32.0/23.0 °c,Out 43.0/26.0 °c	During 2 Hr. protector does not work and Pd < 4.17 Mpa	-	OK	Referent test report no: DEV-25-760-0128	-	OK	Referent test report no: DEV-25-760-0128	
	Cooling Freezing	In21.0/15.0 °c,Out21.0/15.0 °c	6Hr. No ice & water drop from air outlet	-	OK	Referent test report no: DEV-25-760-0128	-	OK	Referent test report no: DEV-25-760-0128	
	Heating overload	In27.0/ - ,Out24.0/18.0 °c	During 2 Hr. protector does not work and Pd < 4.17 Mpa							
	Heating Freezing	Heating low temp.capacity	In20.0/12.0,Out2.0/1.0 °c							
			Q ≥ 97.4% , P ≤ 105.6%							
		Automatic defrost	2 °c,RH95% and ice rmain 10% of Outdoor H/E							
			Time of deforsting must not exeed 20% for heating mode and indoor outlet air							
			is lower 18°c compressor must be not operate 1 min or more							
	Enclosure	JIS condition	RH80%, 4Hr. No water drop from air outlet	-	OK	Referent test report no: DEV-25-760-0128	-	OK	Referent test report no: DEV-25-760-0128	
		Sweatinside	RH80%, 48Hr.ON, 12Hr.OFF, 24Hr.On							
		Evaporating	Refrigerant -50g 4Hr. No water drop							
		Clogged Filter	Gauze (air filter 3, air cleaning filter 6) 4 Hr.							
		In27.0/24.0 °c,Out 27.0/24.0 °c	Indoor RH80%, operated 4Hr. No water drop from air outlet							
	Starting test	JIS condition	Starting voltage minimum ≤ 184 V,Starting current max ≤ - A	-	OK	Referent test report no: DEV-25-760-0128	-	OK	Referent test report no: DEV-25-760-0128	
		Low Temp. Start	Indoor temp. -5°C, outdoot temp. -10°C							
Sound Test	Overall (SPL)	Cooling mode :	Indoor side :	-	OK	Referent test report no: DEV-25-760-0128	1	OK	Indoor side :	
		In DB27.0 °c,WB19.0 °c	Fan Rated = - dBA - rpm not over + 4dBA						Fan Rated = - dBA - rpm < Ane2 >	
		Out DB35.0 °c , WB24.0 °c	Fan Super Hi speed = - dBA - rpm not over + 4dBA						Fan Super Hi speed = - dBA - rpm Feeling 5.0 m. by :	
			Fan Hi speed = - dBA - rpm not over + 4dBA						Fan Hi speed = - dBA - rpm Mr.Pawissanut S.	
			Fan Med speed = - dBA - rpm not over + 4dBA						Fan Med speed = - dBA - rpm	
			Fan Low speed= - dBA - rpm not over + 4dBA						Fan Low speed = - dBA - rpm	
			Fan Super Low speed= - dBA - rpm not over + 4dBA						Fan Super Low speed= - dBA - rpm	
			Outdoor side :						Outdoor side :	
			Front side = 55 dBA 800 rpm not over + 4dBA						Front side = 53.3 dBA 805 rpm ✓	
			Back side = 55 dBA 800 rpm not over + 4dBA						Back side = 54.0 dBA 805 rpm ✓	
	Abnormal noise	Cooling mode :	Feeling check no abnormality noise	-	OK	Referent test report no: DEV-25-760-0128	1	OK	**- Feeling check pipe 5.0 m**	
		In DB27.0 °c,WB19.0 °c	- Pipe length 5 m.						Outddor only : Have refrigerant niose , but no Judement (Refer melshi ,No Jedgement at rated mode for HAC modal)	
		Out DB35.0 °c , WB24.0 °c								
	Other test (Depend on change point)									
Function	Receive of signal remote control		The straight of front > 7 m and Invertor type > 4 m							
	Operating inspection		Operate check confirm by IB				1	OK	Operate check confirm by IB no abnormarmally	
EMC	Impulse noise		Function operate are not abnormal When voltage supply ≤1.8 KV							
	Automatically noise		52C : 3000 times , Relay : 5000 times ON / OFF							
	Withstand voltage		Between lead : 3KV , Earth : 6KV for 30 second 3 times							
	Cut Power Source Immediately		When less than 16.5 ms, no misoperation							
	Electrostatic Endurance		When more than 10 KV , Obstacle operation							
	Noise of voltage terminal (C.E.)		~5 MHz : 56dB , 5 ~ 30 MHz : 60dB							
	Obstacle of electrical wave (R.E./ P.E.)		Not have effects to emission noise 1 m. from TV or Radio							
	Lightning surge		Normal mode 4Kv,Common mode 8Kv do not have fire or smoke							
Safety	Water Spray		Insu. resist. 1M Ω , V power sup. 1500V • 1 min							
	Insulation resistance		10 M Ω or more				1	OK	100 MΩ	
	Dielectric Withstand Voltage		Cut off current 100 mA : Basic Insulation 1000 V / 1 min				1	OK	PASS	
			Supplementary Insulation 1750 V / 1 min				1	OK	PASS	
			Reinforced Insulation 3000 V / 1 min				1	OK	PASS	
	Earthing continuity		25A between earthing and metal parts resistance not exceeding 0.1 Ω				1	OK	Maximum Resistance Value : 0.035Ω	
	Leakage Current		not exceed 2 mA. per Kilowatt of rate power input. (6.18 mA)				1	OK	Maximum Peak : 0.96mA. Cooler (L-E) Stop	
	Temperature rise		The values shall not exceed the safety standard.							
Endurance Ability	Handling test		When lift the handle no damage							
	Band strength		Joint (welding point) 980 N or more							
	Life test(Reliabirity of part)		No damage in standard operating time(2000 ~ 4000hrs)							
	Heat shock		0 ~ 60°c 1hr 10 cycle , no have abnormal and no damage part							
	High temperature stock		55 °c 72hrs Plastic appearance is changing ≤ 1mm.							
Final Inspection	DT Packing Inspection		Accessories , IB , IM ,Guarantee must be packing and check				1	OK	PASS	
	Fuction Test at Production Line		Can operate comply with model funtion				1	OK	PASS	
	PQI Packing Inspection		Accessories , IB , IM ,Guarantee must be packing and check				1	OK	PASS	

2. Main problem :

No.	Problem	Cause / Reason	Countermeasure	Judgement

COMMENT :