

RAC PERFORMANCE DATA

CONFIDENTIAL

Model Name : MSY-KA09VF-TH1 / MUY-KA09VF-TH1
Power supply : 1 Ø 50 Hz 230 V
Comp.model : KVB065FXDMC
Ref.weight : (R32) = 290 g.
C / T size : C/T:φ3.0-1.2*900L mm.
LEV :
Reference design specification no. : 702-RA-25068

Indoor unit : MSY-KA09VF-TH1
-Production date : 8-Jan-26 Line : A
-Lot size : 60000801-60001000 Units 200
Outdoor unit : MUY-KA09VF-TH1
-Production date : 26-Feb-26 Line : C
-Lot size : 60018656-60018855 Units 200
Period of test : 15 May - 2 Jun 2026

APPROVE (QA.Dept.Mgr.)	APPROVE (Dev. Test SM)	CHECKE	RECORD
REPORT NO.	SAM-26-760-0005		

Reference Product standard : TIS 2134-2565
Reference Capacity and Performance test standard : TIS 2134-2565
Reference Sound test standard : ISO 3744:2025, ISO 3745:2012 + Amendment 1:2017
Reference Safety test standard : TIS 1155-2557, TIS1529-2561
Reference Other test standard : EGAT (Electricity Generating Authority of Thailand)

1. Test result :

Classification of Evaluate Item		Specification and Tolerance		Qty	Judg	Data test result	
Test	Item	Condition					
Cooling - Heating Capacity and General Performance	Cooling capacity [Rate]	Room temp. In DB27.0°C, WB19.0°C Out DB35.0°C, WB24.0°C	Spec. 1 φ, 50 Hz, 230 V Capacity = 2700 W ≥ 97.2 % Power input = 865 W ≤ 110.0 % EER = 3.12 W/W ≥ 95.2 % SEER (Label) = 18.50 Btu/h.w ≥ 95.2 % and ≥ 17.06 EGAT Energy rating = No.5 Comp. Hz. = 76.0 Hz. Td = - Pipe length = 7.5 m.	1	OK	S / N : 60000899 / 60018797 [RA-11] Capacity = 2658.9 W (98.478%) Power input = 843.6 W (97.526%) EER = 3.152 W/W (101.026%) SEER (Label) = 17.740 Btu/h.w (95.892%) EGAT Energy rating = No.5 Comp. Hz. = 76.0 Hz. Td = 86.1 °C Pipe length = 7.5 m.	
	Cooling capacity [Half load]	Room temp. In DB27.0°C, WB19.0°C Out DB35.0°C, WB24.0°C	Spec. 1 φ, 50 Hz, 230 V Capacity = 1329.4 W (Rate / 2) Q ± 132.9 W and ± 5 % of actual rate Power input = 277 W ≤ - % EER = 4.87 W/W ≥ - % Pipe length = 7.5 m.	1	OK	S / N : 60000899 / 60018797 [RA-11] Capacity = 1334.2 W (100.181%) Power input = 287.9 W (103.935%) EER = 4.635 W/W (95.175%) Pipe length = 7.5 m.	
	Cooling overload	In 32.0 / 23.0, Out 43.0/26.0 °C	During 2 Hr. protector does not work and Pd < 4.17 MPa.	1	OK	Td. Max : 104.4 °C (220 V) , Max Pd. = 3.533 MPa. (242 V.)	
	Starting test	In 32.0 / 23.0, Out 43.0/26.0 °C	Low voltage start ≤ 176 V	1	OK	Starting voltage = 157.5.0V (71.6%)	
	Freezing disturbance	In 21.0 / 15.0, Out 12.0 / 15 °C	Ice on indoor coil surface not over 10% of indoor coil area	1	OK	Have not ice on cooler surface and have not water blow out from nozzle.	
	Freezing dripping	In 21.0 / 15.0, Out 12.0 / 15 °C	6Hr. No ice & water drop from air outlet	1	OK	Have not ice on cooler surface and have not water blow out from nozzle.	
	Heating overload	In 27.0 / - , Out 24.0 / 18.0 °C	Voltage ± 10% operate 2 Hr. protector does not work				
	Automatic defrost	Low temp High Humidity ratio In 20.0 / 12.0, Out 2.0 / 1.0 °C	Frost remain less than 1 / 3 of outdoor coil and during melting frost have not abnormal noise.				
	Enclosure Sweat	In 27.0 / 24.0, Out 27.0/24.0 °C	RH80%, operate 4Hr. indoor fan low must be no water drop from air air outlet and disposal of condensated water not found.	1	OK	No condensated water drop and not blow out from nozzle.	
	Other test (Depend on change point)						
Sound	Overall (SPL)	Cooling mode : In DB27.0°C, WB19.0°C Out DB35.0°C, WB24.0°C	Indoor side : Fan Rated Hi speed = 43 dBA 930 rpm not over + 4dBA Fan Super Hi speed = 43 dBA 930 rpm not over + 4dBA Fan Hi speed = 37 dBA 760 rpm not over + 4dBA Fan Med speed = 31 dBA 650 rpm not over + 4dBA Fan Low speed = 25 dBA 530 rpm not over + 4dBA Fan S.Low speed = 19 dBA 450 rpm not over + 4dBA Outdoor side : Front side = 52 dBA 980 rpm not over + 4dBA Back side = 52 dBA 980 rpm not over + 4dBA	1	OK	Indoor side : Fan Rated = 37.8 dBA 928 rpm Feeling 5.0 m. By Fan Super Hi speed = 37.2 dBA 926 rpm Mr. Armont N. Fan Hi speed = 30.5 dBA 762 rpm Mr. Chaiyasit O. Fan Med speed = 26.5 dBA 658 rpm Fan Low speed = 23.2 dBA 532 rpm Fan Super Low speed = 21.2 dBA 455 rpm Outdoor side : Front side 230V = 50.7 dBA 986 rpm Back side 230V = 52.0 dBA 986 rpm	
	Abnormal noise	Cooling mode : In DB27.0°C, WB19.0°C Out DB35.0°C, WB24.0°C	Feeling check no abnormality noise - Pipe length 5 m.	1	OK	Indoor start fan low and super low cool mode have refrigerant noise and compressor noise level low. Indoor stop cool mode have refrigerant noise and compressor noise level low. Outdoor start and stop cool mode have efrigerant noise and compressor noise level low.	
	Overall (SPL)	Heating mode : In DB20.0°C, WB - °C Out DB7.0°C, WB6.0°C	Indoor side : Fan Rated Hi speed = dBA (rpm) not over + 4dBA Fan Super Hi speed = dBA (rpm) not over + 4dBA Fan Hi speed = dBA (rpm) not over + 4dBA Fan Med speed = dBA (rpm) not over + 4dBA Fan Low speed = dBA (rpm) not over + 4dBA Outdoor side : Front side = dBA (rpm) not over + 4dBA Back side = dBA (rpm) not over + 4dBA	-	-		
	Abnormal noise	Heating mode : In DB20.0°C, WB - °C Out DB7.0°C, WB6.0°C	Feeling check no abnormality noise - Pipe length 5 m.	-	-		
	Other test (Depend on change point)						
	Impulse noise		Function operate are not abnormal When voltage supply £ 1.8 KV				
	Operating characteristic		Operate check confirm by IB				
	Other test (Depend on change point)						
	Insulation resistance		10 MΩ or more / 500 V.	1	OK	100 MΩ	
	Dielectric Withstand Voltage		Cut off current 100 mA : Basic Insulation 1000 V / 1 min Supplementary Insulation 1750 V / 1 min Reinforced Insulation 3000 V / 1 min	1	OK	PASS	
Safety	Earthing continuity		25A between earthing and metal parts resistance not exceeding 0.1 Ω	1	OK	PASS	
	Leakage Current		Not exceed 2 mA. per Kilowatt of max power input. (2.96 mA)	1	OK	Max Peak : 0.37 mA. Cabinet (N-E) Stop	
	Other test (Depend on change point)						
	DT Packing Inspection		Accessories , IB , IM , Guarantee must be packing and check	1	OK	PASS	
Final Inspection	Fuction Test at Production Line		Can operate comply with model funtion	1	OK	PASS	
	PQI Packing Inspection		Accessories , IB , IM , Guarantee must be packing and check	1	OK	PASS	

2. Problem

No.	Detail	Cause	Improvement	Judgement
-----	--------	-------	-------------	-----------

COMMENT :

ตารางที่ 7 เปรียบเทียบประสิทธิภาพการทำงานของเครื่องปรับอากาศ ชนิด Variable Speed/Inverter

ขนาดห้องปรับอากาศ	ค่าประสิทธิภาพ : SEER (BTU/h/วัตต์)					
	15	15	15	15	15	15
15,000 BTU/h (4,224 W)	17.06 - 18.55	18.56 - 20.05	20.06 - 21.55	21.56 - 23.05	23.06 - 24.55	≥ 24.56
18,000 BTU/h (5,224 W)	16.03 - 17.15	17.16 - 18.27	18.28 - 19.38	19.39 - 20.50	20.51 - 21.62	≥ 21.63
24,000 BTU/h (7,000 W)	14.00 - 15.49	15.50 - 16.99	17.00 - 18.49	18.50 - 19.99	20.00 - 21.49	≥ 21.50